# NOTICE OF INTENT

# LOT 9

THE WINSLOW DRIVE REALTY GROUP, LLC 17 WINSLOW DRIVE ATKINSON, NH 03811

#### INDEX OF SHEETS

I OF 4 COVER SHEET & GENERAL NOTES

3 OF 4 BMP & SITE DETAILS

4 OF 4 EROSION CONTROL DETAILS

#### ZONING DISTRICT

R-A RESIDENTIAL - AGRICULTURAL DISTRICT MINIMUM LOT SIZE

(6 ACRES FOR REDUCED

FRONTAGE LOT) = 250' (50' FOR REDUCED

FRONTAGE LOT) MINIMUM LOT WIDTH = 200' DIAMETER CIRCLE

PERCENT COVERAGE = BUILDINGS LESS THAN 25%

OF THE LOT AREA MINIMUM SET BACKS:

FRONT = 50'

SIDE = 25' REAR = 25'

#### REFERENCES

ASSESSORS MAP II BLOCK I LOTS 1,2,16,17,26.5

BK. 3728 PG. 203

ESSEX CO. PRO. 05P2650EPI SIEGERT: BK. 23276 PG. 483

PLANS PL. BK. 134 PL.18

PL. BK. 318 PL. 76 PL. BK. 91 PL. 73


L.C. PLAN 25371D

1931 COUNTY LAYOUT #2486

PL. BK. 258 PL. 41 PL. BK. 245 PL. 47

NOT IN A HAZARD ZONE SHOWN ON F.I.R.M. 250078

0002 C, DATED 6-3-91 VERTICAL DATUM: NGVD, 1929



### LOCATION PLAN

SOURCE: MA GIS DIGITAL RASTER GRAPHIC (DRG)

CURRENT OWNERS: BARBARA M. SIEGERT, TRUSTEE BARBARA M. SIEGERT REALTY TRUST PHILIP A. JR. & ANNA MARIE BUSBY

ALL OF THE UNDERGROUND UTILITIES ARE NOT SHOWN ON THIS PLAN. CONTACT INDIVIDUAL UTILITY COMPANIES TO DETERMINE THE LOCATION OF THE LINES. BEFORE DESIGN AND CONSTRUCTION CALL "<u>DIG SAFE</u>" AT I-800-DIG SAFE

#### PROJECT GENERAL NOTES

- EXISTING BOUNDARY LINE, TOPOGRAPHIC, AND SITE UTILITY INFORMATION IS BASED UPON FIELD SURVEY PERFORMED BY DONOHOE SURVEYING, INC.
- 2. PRIOR TO WORK, CONTRACTOR SHALL HAVE THE PROPOSED SITE LAID OUT VERTICALLY AND HORIZONTALLY BY A PROFESSIONAL LAND SURVEYOR.
- 3. IN ACCORDANCE WITH CHAPTER 82 SECTION 40 INCLUDING AMENDMENTS, THE CONTRACTOR SHALL NOTIFY IN WRITING ALL UTILITY COMPANIES AND GOVERNMENT AGENCIES PRIOR TO EXCAVATION WORK AND CALL DIG-SAFE AT I-800-DIG-SAFE PRIOR TO COMMENCING WORK.
- THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVES. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTORS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES
- WHERE AN EXISTING UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, THE LOCATION, ELEVATIONS, AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY THE CONTRACTOR AND THE INFORMATION FURNISHED TO THE ENGINEER FOR RESOLUTION OF THE CONFLICT.
- 6. CONTRACTOR SHALL FIELD VERIFY AND LOCATE ALL EXISTING UTILITIES AND REPORT ANY DISCREPANCIES TO THE ENGINEER PRIOR TO COMMENCING WORK.
- 7. CONTRACTOR SHALL PROVIDE ADEQUATE BRACING AND SHORING OF ALL EXCAVATIONS IN ACCORDANCE WITH THE REQUIREMENTS OF ALL GOVERNING CODES AND REGULATIONS.
- 8. CONTRACTOR SHALL COORDINATE WITH THE STATE POLICE DEPARTMENT FOR TRAFFIC RELATED ISSUES PRIOR TO COMMENCING WORK. CONTRACTOR SHALL PROVIDE ALL NECESSARY TRAFFIC COORDINATION AND POLICE DETAILS AS REQUIRED BY THE STATE.
- CONTRACTOR SHALL SAW-CUT PAVEMENT WHERE PAVEMENT TO BE REMOVED ABUTS PAVEMENT WHICH IS TO REMAIN AND WHERE NEW PAVEMENT ABUTS EXISTING PAVEMENT.
- 10. CONTRACTOR SHALL MAINTAIN ALL NEW AND EXISTING UTILITIES IN GOOD WORKING ORDER AND SHALL PROTECT THEM FROM DAMAGE AT ALL TIMES THROUGHOUT CONSTRUCTION UNTIL WORK IS COMPLETED AND ACCEPTED.
- II. PINERIDGE SUBDIVISION DEP #II4-II51 PINERIDGE SUBDIVISION.

#### CONSULTANTS:

CIVIL ENGINEER: ASB DESIGN GROUP, LLC 363 BOSTON STREET TOPSFIELD MA 01983 978.887.6161

SURVEYOR:

DONOHOE SURVEY, INC. 363 BOSTON STREET TOPSFIELD MA 01983 978.887.6161

**WETLANDS:** RIMMER ENVIRONMENTAL CONSULTING, LLC 30 GREEN STREET NEWBURYPORT MA 01950 978.463.9226

#### PROJECT BENCHMARK:

FROM BOXFORD MA TOWN\* "PINERIDGE SUBDIVISION PROJECT"

BENCHMARK: STA 13+91.11 85.98' RT

CUT SPIKE IN 24" PINE TREE ELEV. = 139.39

BENCHMARK: STA 18+41.40 61.90' RT

CUT SPIKE IN UTILITY POLE #2108/4 ELEV. = 143.96

design group, LLC

landscape design & construction

civil engineering traffic engineering architecture

363 boston street, route 1 topsfield, ma 01983

project title:

# PINERIDGE SUBDIVISION

prepared for:

THE WINSLOW DRIVE REALTY GROUP, LLC 24 WINSLOW DRIVE ATKINSON, NH 03811

revisions


no.	date	description
0	08.06.15	ISSUED FOR REVIEW

plan submission

NOTICE OF INTENT LOT 9

08.06.2015 job no: <u>2011-57</u> / <u>2704</u>

DEP no: <u>114 - 1151 ROADWAY</u>




drawing name

COVER SHEET \$ GENERAL NOTES

drawing number






REALTY GROUP, LLC 24 WINSLOW DRIVE

no.	date	description
0	08.06.15	ISSUED FOR REVIEW

DEP no: <u>114 - 1151 ROADWAY</u>



# INFILTRATION CALCULATIONS:

TEXTURE CLASS	HYDROLOGIC SOIL GROUP (HSG)	RATE (INCHES/HOUR)
SAND	A	8.27
LOAMY SAND	A	2.41
SANDY LOAM	В	1.02
LOAM	B	0.52
SILT LOAM	C	0.27
SANDY CLAY LOAM	C	0.17
CLAY LOAM	D	0.09
SILTY CLAY LOAM	D	0.06
SANDY CLAY	D	0.05
SILTY CLAY	D	0.04
CLAY	D	0.02


INFILTRATION

POND | AREA = 10 X 19.5' = 195.0 SQFT

#### INFILTRATION FOR ROOF - BMP #1 ("STATIC" METHOD)


- INFILTRATION RATE: 8,27 IN/HR
- $-Q = (K) \times (BOTTOM AREA) = (8.27 IN/HR) \times (195.00') \times \frac{(1' \times 1 HR)}{(12'' \times 3600 sec)}$
- -Q = .037 cfs SAY 0.04
- $\vee$  =  $\frac{41.8 \text{ cf}}{10\text{NIT}} \times 4 \text{ UNITS} = 167.2 \text{ cf} (CULTECH C-100 OR EQUAL)$
- DRAWDOWN TIME =  $\frac{\vee}{Q}$  < 72 HOURS
- DRAWDOWN TIME =  $\frac{1600}{.040} \times \frac{1 \text{ HR}}{3,600 \text{ sec}} = 11.1 \text{ HOURS}$

IF DOWN SPOUTS ARE NOT USED THE CONTRACTOR SHALL INSTALL A STONE DRIP EDGE (12" WIDE MINIMUM) AT ALL ROOF DRIP EDGES THAT DISCHARGES STORMWATER ROOF RUNOFF.



#### DRIP EDGE DETAIL

NOT TO SCALE



#### TYPICAL PAVEMENT SECTION DRIVEWAY

NOT TO SCALE

— CLEAN BACKFILL

FINISH GRADE


- YELLOW METALLIC WARNING

TAPE 12" BELOW GRADE

PROVIDE 36" COVER MIN.

COORDINATE WITH LOCAL UTILTIY

— CLEAN BACKFILL FINISH GRADE BLUE METALLIC WARNING TAPE 12" BELOW GRADE SAND -TYPE 'K' WATER SERVICE COORDINATE WITH LOCAL UTILITY



Technical Information

The Contactor® 100HD is a 12.5" (318 mm) tall, low

profile chamber and is typically used for installations with depth restrictions or when a larger infiltrative

area is required. The Contactor 100HD has the side portal internal manifold feature. The HVLV™ SFCx2

Feed Connector is inserted into the side portal of the

8' x 36" x 12.5"

2.29 m

1.87 ft3/ft

0.17 m<sup>3</sup>/m

14.00 ft3/unit

0.40 m³/unit

28.81 ft<sup>3</sup>/unit

0.82 m³/unit

25 ft<sup>2</sup> 2.32 m<sup>2</sup>

1.02 m

4.27 m

Chamber and Stone Storage 28.81 ft<sup>3</sup> 33.81 ft<sup>3</sup> 38.81 ft
Per Chamber

Stone Required Per Chamber 1.37 yd3 1.84 yd3 2.30 yd

Calculations are based on installed chamber length.
Includes 6" (152 mm) stone above crown of chamber and typical stone surround.
Stone void calculated at 40%.

178 mm x 191 mm

HVLV™ SFCx2 Feed Connecto

6" 12" 18'

152 mm 305 mm 457 mm

0.62 m 0.77 m 0.93 m

1.05 m<sup>3</sup> 1.40 m<sup>3</sup> 1.76 m<sup>3</sup>

3.84 ft3/ft 0.36 m<sup>3</sup>/m

0.5' 0.15 m

2.44 m x 914 mm x 318 mm

Contactor® 100HD Bare Chamber Storage Volumes

Total 1.866 0.173 13.995 0.396 13.995 0.396

LOAM & SEED BMP ACCESS DRIVE

NOT TO SCALE

3'-0"

STORMWATER INFILTRATION

TRENCH/PIPE

NOT TO SCALE

OTHER PROPERTY OF THE STATE OF

- CLEAN BACKFILL

Calculations are based on installed chamber length.

Contactor 100HD to create the internal manifold.

Installed Length

Chamber Storage

Min. Installed Storage

Min. Area Required

Max. Allowable Cover

Max. Allowable Pipe Size in Side Portal

– ESTABLISHED TURF PER

CLEAN FILL OR SUBSOIL

NOT TO SCALE

MEADOW GRASS

SEED BMP # WITH NATIVE

WILD FLOWER

MEADOW GRASS AND

WILD FLOWER SEED MIX.

LOAM & SEED NOTES

Compatible Feed Connector

Min. Center to Center Spacing 3.33'

Max. Inlet Opening in Endwall 10"

Side Portal Dimensions (H x W) 7" x 7.5"

Length Adjustment per Run

**CULTEC Contactor® 100HD** 

INFILTRATION NFILTRATION SYSTEM A SYSTEM B - INSPECTION PORT (TYP.) STONE HEADWALL STORMWATER INFILTRATION TRENCH/PIPE - 12' WIDE DPW ACCESS DRIVE FOR CATCH BASIN CLEANING BMP #1

> <u>CBIA</u> RIM=123.00 INV. (IN - CB#1)=120.30 (8" PPVC) INV. (OUT TO CULTEC CHAMBERS)=120.30 (10" ADS N-12)

HYDROCAD MODEL AREA=48.50'x14.00'=679.00 S.F.

SCALE: I"=10'

OVERFLOW PIPE INV. @ A=125.00

INV. @ B=122.50

6'-6" ADS N-12

EXISTING -GRADE

CULTEC C-100 CONTACTOR INV. (INTO CULTEC CHAMBERS)=120.50 BOTTOM OF STONE INFILTRATION AREA=119.50 9 CHAMBERS FOR INFILTRATION SYSTEM A 9 CHAMBERS FOR INFILTRATION SYSTEM B TOTAL AREA (A&B)=2(25.75'x14.00')=721.00 S.F.

HEADWALL 124 CBIA

INFILTRATION INFILTRATION SYSTEM B SYSTEM A DESIGN ELEVATION = 124.75 S.H.W.T. NONE AT 116.5 BOTTOM OF INFILTRATION SYSTEM = 119.50 3' TO S.H.W.T

CROSS SECTION A-A

HOR. SCALE: 1"=10' VERT. SCALE = I"=I"

design group, LLC

civil engineering traffic engineering

architecture landscape design & construction

363 boston street, route 1 topsfield, ma 01983

project title:

# PINERIDGE SUBDIVISION

prepared for:

THE WINSLOW DRIVE REALTY GROUP, LLC 24 WINSLOW DRIVE ATKINSON, NH 03811

revisions

no.	date	description
0	08.06.15	ISSUED FOR REVIEW


plan submission

124

NOTICE OF INTENT LOT 9

<u>08.06.15</u> date: scale: 2011-57 / 2704

DEP no: <u>114 - 1151 ROADWAY</u>



drawing name

BMP & SITE DETAILS

drawing number



## GAS SERVICE TRENCH

- GAS SERVICE

SAND -

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

WELL/WATER SERVICE TRENCH

- ESTABLISHED TURF PER

GRADED & COMPACTED

OVERFLOW

120

EXISTING SUBGRADE


34" WASHED STONE


- FILTER FABRIC

- 8" PPVC

LOAM & SEED DETAIL NOTES

SERVICE TRENCH






SILTATION SOCK DETAIL

NOT TO SCALE


TABLE #I			
SLOPE	SOCK DIAMETER (MIN.)	STAKING	2" COMPOST BARRIER (WOOD CHIPS)
< 50:I	9"	6' O.C.	
50:1 TO 10:1	9"	6' O.C.	
10:1 TO 5:1	12"	6' O.C.	
3:1 TO 2:1	12"	4' O.C.	
> 2:1	18"	4' O.C.	RECOMMENDED
> 2:1	18"	4' 0.6.	RECOMMENDED

#### INSTALLATION NOTES:

- I. INSTALL SILT SOCK ON A SURFACE CLEAR OF DEBRIS.
- 2. OVERLAP ENDS BY A MINIMUM OF 18-INCHES.
- 3. END OF SILT SOCK TO BE DIRECTED UP SLOPE.
- 4. PLACE STAKES THROUGH SILT SOCK OR ON DOWNSTREAM SIDE.
- 5. ON SLOPES GREATER THAN 2:1 (>2:1) SEED COMPOST SOCK IS RECOMMENDED.



#### SECTION A - A




- NOTES:

  I. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.
- 2. WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.
- 3. ADJACENT STREETS SHALL BE SWEPT AS REQUIRED BY OMI (SHEET 10 OF 12).

# TEMPORARY CONSTRUCTION ENTRANCE

NOT TO SCALE



WASHOUT BASIN

NOT TO SCALE

(150-380mm)

GROOVE BY CUTTING SERRATIONS ALONG THE CONTOUR. IRREGULARITIES IN THE SOIL SURFACE


CATCH RAINWATER, SEED, MULCH AND FERTILIZER.

GROOVED OR SERRATED SLOPE

NOT TO SCALE

(25-75mm)

LATTER



#### EROSION CONTROL NOTES

EROSION CONTROL PRINCIPLES

- A. THE FOLLOWING EROSION CONTROL PRINCIPLES SHALL APPLY TO THE LAND GRADING AND CONSTRUCTION PHASES:
- I) STRIPPING OF VEGETATION, GRADING, OR OTHER SOIL DISTURBANCE SHALL BE DONE IN A MANNER WHICH WILL MINIMIZE SOIL EROSION.
- 2) WHENEVER FEASIBLE, NATURAL VEGETATION SHALL BE RETAINED AND PROTECTED
- 3) EXTENT OF AREA WHICH IS EXPOSED AND FREE OF VEGETATION AND DURATION OF ITS EXPOSURE SHALL BE KEPT WITHIN PRACTICAL LIMITS.
- 4) TEMPORARY SEEDING, MULCHING, OR OTHER SUITABLE STABILIZATION MEASURES SHALL BE USED TO PROTECT EXPOSED CRITICAL AREAS DURING PROLONGED CONSTRUCTION OR OTHER LAND DISTURBANCE.
- 5) DRAINAGE PROVISIONS SHALL ACCOMMODATE INCREASED RUNOFF RESULTING FROM MODIFICATIONS OF SOIL AND SURFACE CONDITIONS DURING AND AFTER DEVELOPMENT OR DISTURBANCE. SUCH PROVISIONS SHALL BE IN ADDITION TO EXISTING REQUIREMENTS.
- 6) SEDIMENT SHALL BE RETAINED ON-SITE.
  7) EROSION CONTROL DEVICES SHALL BE INSTALLED AS EARLY AS POSSIBLE IN THE CONSTRUCTION SEQUENCE PRIOR TO START OF CLEARING AND

GRUBBING OPERATIONS AND EXCAVATION WORK.

- B. CUT AND FILL SLOPES AND STOCKPILED MATERIALS SHALL BE PROTECTED TO PREVENT EROSION. SLOPES SHALL BE PROTECTED WITH PERMANENT EROSION PROTECTION WHEN EROSION EXPOSURE PERIOD IS GREATER THAN OR EQUAL TO SIX MONTHS, AND TEMPORARY EROSION PROTECTION WHEN EROSION EXPOSURE PERIOD IS EXPECTED TO BE LESS THAN SIX MONTHS (SEE NOTE 18).
- I) PERMANENT EROSION PROTECTION SHALL BE ACCOMPLISHED BY SEEDING WITH GRASS AND COVERING WITH AN EROSION PROTECTION MATERIAL, AS APPROPRIATE FOR PREVAILING CONDITIONS.
- 2) EXCEPT WHERE SPECIFIED SLOPE IS INDICATED ON DRAWINGS, FILL SLOPES SHALL BE LIMITED TO A GRADE OF 3:1 (HORIZONTAL: VERTICAL) AND CUT SLOPES SHALL BE LIMITED TO A GRADE OF 3:1.

#### HAY BALES DIKE

BALES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT BALES. EACH BALE SHALL BE EMBEDDED IN THE SOIL A MINIMUM OF 4-INCHES. BALES SHALL BE SECURELY ANCHORED IN PLACE BY STAKES OR REBAR DRIVEN THROUGH THE BALES. THE FIRST STAKE IN EACH BALE SHALL BE ANGLED TOWARD THE PREVIOUSLY LAID BALE TO FORCE THE BALES TOGETHER

#### MAINTENANCE AND REMOVAL OF CONTROL DEVICES

- A. WETLAND AREAS, WATER COURSES, AND DRAINAGE SWALES ADJACENT TO CONSTRUCTION ACTIVITIES SHALL BE MONITORED TWICE EACH MONTH FOR EVIDENCE OF SILT INTRUSION AND OTHER ADVERSE ENVIRONMENTAL IMPACTS, WHICH SHALL BE CORRECTED IMMEDIATELY UPON DISCOVERY.
- B. CULVERTS AND DRAINAGE DITCHES SHALL BE KEPT CLEAN AND CLEAR OF OBSTRUCTIONS DURING CONSTRUCTION PERIOD.
- C. EROSION CONTROL DEVICES:
- I) SEDIMENT BEHIND THE EROSION CONTROL DEVICE SHALL BE CHECKED TWICE EACH MONTH AND AFTER EACH HEAVY RAIN. SILT SHALL BE REMOVED IF GREATER THAN 6-INCHES DEEP.
- 2) CONDITION OF EROSION CONTROL DEVICE SHALL BE CHECKED TWICE EACH MONTH OR MORE FREQUENTLY AS REQUIRED. DAMAGED AND/OR DETERIORATED ITEMS SHALL BE REPLACED. EROSION CONTROL DEVICES SHALL BE MAINTAINED IN-PLACE AND IN EFFECTIVE CONDITION.
- 3) HAY BALES SHALL BE INSPECTED FREQUENTLY AND MAINTAINED OR REPLACED AS REQUIRED TO MAINTAIN BOTH EFFECTIVENESS AND INSTALLED CONDITION. UNDERSIDE OF BALES SHALL BE KEPT IN CLOSE CONTACT WITH THE EARTH BELOW AT ALL TIMES, AS REQUIRED TO PREVENT WATER FROM WASHING BENEATH BALES.
- 4) SEDIMENT SHALL BE REMOVED FROM THE RETENTION PONDS AT THE COMPLETION OF THE PROJECT AND PERIODICALLY DURING CONSTRUCTION. SEDIMENT DEPOSITS SHALL BE REMOVED WHEN SEDIMENT HAS ACCUMULATED TO A DEPTH OF 6 INCHES, OR AS DIRECTED.
- 5) SEDIMENT DEPOSITS SHALL BE DISPOSED OF OFF-SITE, IN A LOCATION AND MANNER WHICH WILL NOT CAUSE SEDIMENT NUISANCE ELSEWHERE.
- D. REMOVAL OF EROSION CONTROL DEVICES:
- I) EROSION CONTROL DEVICES SHALL BE MAINTAINED UNTIL ALL DISTURBED EARTH HAS BEEN PAVED OR VEGETATED, AT WHICH TIME THEY SHALL BE REMOVED. AFTER REMOVAL, AREAS DISTURBED BY THESE DEVICES SHALL BE RE-GRADED AND SEEDED.
- 2) EROSION CONTROL NETTING SHALL BE KEPT SECURELY ANCHORED UNTIL START OF PERMANENT TURF CONSTRUCTION.
- 3) EROSION PROTECTION MATERIAL SHALL BE KEPT SECURELY ANCHORED UNTIL ACCEPTANCE OF COMPLETED SLOPE OR ENTIRE PROJECT, WHICHEVER IS LATER.

# ASB

design group, LLC

civil engineering traffic engineering

architecture
landscape design & construction

363 boston street, route 1 topsfield, ma 01983

project title:

# PINERIDGE SUBDIVISION

prepared for:

THE WINSLOW DRIVE REALTY GROUP, LLC 24 WINSLOW DRIVE ATKINSON, NH 03811


revisions

	no.	date	description
	0	08.06.15	ISSUED FOR REVIEW

plan submission

NOTICE OF INTENT LOT 9

date:	08.06.15
scale:	_1"=20'
job no:	<u>2011-57</u> / <u>2704</u>
DEP no:	114 - 1151 ROADV



drawing name

EROSION CONTROL DETAILS

drawing number



sheet 4 of 4