

DRAFTED BY BFS

REV

COMMENTS

DATE

## CONSTRUCTION NOTES/CONSTRUCTION SEQUENCING

- INSTALL SEDIMENTATION AND EROSION CONTROLS PRIOR TO BEGINNING WORK.
- 2. ALL WORK SHALL BE CLOSELY COORDINATED WITH THE BOXFORD CONSERVATION COMMISSION OR THEIR DESIGNEE.
- 3. ALL IN-STREAM WORK SHALL BE COORDINATED SO THAT CULVERT REMOVAL AND NEW CULVERT INSTALLATION BEGINS AND IS COMPLETED DURING A PERIOD OF "LOW FLOW" CONDITIONS AND IS PERFORMED IN ACCORDANCE WITH THE ORDER OF CONDITIONS. CONTRACTOR'S PROPOSED WORK SCHEDULE AND VERIFICATION OF WEATHER CONDITIONS SHALL BE SUBMITTED TO THE BOXFORD DEPARTMENT OF PUBLIC WORKS FOR REVIEW AND APPROVAL PRIOR TO COMMENCING WORK.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTROL OF WATER AND STORM WATER AT ALL TIMES INCLUDING BUT NOT LIMITED TO MAINTAINING, REPLACING AND RE-FASTENING EROSION AND SEDIMENTATION CONTROL DEVICES AS NEEDED TO PREVENT SEDIMENT FROM LEAVING THE SITE AND ENTERING WETLAND RESOURCE AREAS.
- 5. EXISTING STREAMBED MATERIAL SHALL BE STOCKPILED SEPARATELY FOR REUSE. ADDITIONAL STREAMBED MATERIAL SHALL CONSIST OF CLEAN GRANULAR MATERIAL WITH THE SAME GRADATION AS THE EXISTING STREAM CHANNEL. STREAMBED MATERIAL SHALL BE DURABLE WASHED ROUNDED AGGREGATE FREE OF FINES, ORGANIC AND DELETERIOUS MATERIAL. CONCRETE, BRICK AND OTHER CONSTRUCTION DEBRIS IS PROHIBITED. THE ENGINEER SHALL APPROVE MATERIAL PRIOR TO PLACEMENT.
- 6. THE REFUELING OF VEHICLES AND/OR THE STOCKPILING OF NEW OR EXCAVATED FILL MATERIALS WITHIN 100 FEET OF THE STREAM SHALL NOT BE PERMITTED.
- 7. WORK IN WETLAND RESOURCE AREAS SHALL BE CONDUCTED MANUALLY. WITH EXCEPTION OF HAND HELD TOOLS, NO MECHANICAL EQUIPMENT SHALL BE OPERATED WITHIN THE RESOURCE AREA.
- DISTURBED AREAS AND SLOPES SHALL BE STABILIZED WITH APPROVED SEED MIX, PLANTINGS AND/OR EROSION CONTROL BLANKET, AS NECESSARY, AS SHOWN ON THE PLANS. SEED MIX AND EROSION CONTROL BLANKET SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S REQUIREMENTS.
- DEBRIS FROM CONSTRUCTION THAT FALLS INTO THE RESOURCE AREA WILL BE REMOVED PRIOR TO THE COMPLETION OF EACH WORKDAY.
- 10. ALL DISTURBED LAND UNDER WATER AREAS SHALL BE STABILIZED AS INDICATED ON THE PLANS, DETAILS AND SECTIONS, OR AS DIRECTED BY THE ENGINEER OR THE TOWN PRIOR TO REMOVING WATER CONTROL MEASURES.
- 11. EROSION AND SEDIMENTATION CONTROLS SHALL BE REMOVED AFTER COMPLETION AND ACCEPTANCE OF ALL WORK AND WHEN AUTHORIZED BY THE BOXFORD CONSERVATION COMMISSION OR DESIGNEE.

#### WORK IN VEGETATED WETLAND AREAS

- 1. WETLAND SOIL SHALL BE EXCAVATED TO A DEPTH OF 12 INCHES, AND STOCKPILED AND COVERED WITH BURLAP OR STRAW MULCH TO RETAIN MOISTURE. PERIODIC LIGHT APPLICATION OF WATER MAY BE REQUIRED TO MAINTAIN MOISTURE.
- 2. WETLAND SOIL SHALL BE RESPREAD 12 INCHES DEEP AND LIGHTLY COMPACTED BY HAND
- 3. WETLAND SEED MIX SHALL BE APPLIED AT A RATE OF ½ LB./1000 SQUARE FEET AND LIGHTLY RAKED TO ENSURE SOIL/SEED CONTACT.
- 4. WETLAND SEED MIX SHALL BE PURE LIVE SEED AND CONTAIN NATIVE NON-HYBRIDIZED SPECIES. SEED MIX SPECIES LIST SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO APPLICATION.

## PLAN REFERENCES:

1. PLAN ENTITLED "SITE PLAN IN BOXFORD, MA"; PREPARED FOR THE TOWN OF BOXFORD BY DONOHOE AND SURVEY, INC.; SCALE 1"=10'; DATED NOVEMBER 17, 2014; REV DECEMBER 1, 2014

## **VEGETATED AREAS/SLOPES:**

4" LOAM AND SEED WITH EROSION CONTROL BLANKET (ON 3:1 SLOPE OR LESS USE NORTH AMERICAN GREEN S75BN SINGLE NET EROSION CONTROL BLANKET; ON SLOPES GREATER THAN 3:1 USE NORTH AMERICAN GREEN SC150BN DOUBLE NET EROSION CONTROL BLANKET, OR ENGINEER APPROVED EQUAL.)

## PAVEMENT NOTES:

ROADWAY PAVEMENT: (FULL DEPTH RECONSTRUCTION)

**SURFACE COURSE:** 3-1/2" HOT MIX ASPHALT PAVEMENT PLACED IN TWO LAYERS, 1-1/2" TOP COURSE MATERIAL OVER 2" BINDER COURSE MATERIAL

BASE COURSE: 3" HOT MIX ASPHALT BASE COURSE MATERIAL, PLACED IN ONE LAYER.

SUBBASE: 12" GRAVEL BORROW

## TEMPORARY PATCH:

3" HOT MIX ASPHALT BASE COURSE MATERIAL PLACED IN ONE LAYER.

SUBBASE: GRAVEL BORROW


DATUM NAVD 88


**BOXFORD, MASSACHUSETTS** Land Surveying


Transportation Engineering PREPARED FOR: Architectural Design & Building Renovations TOWN OF BOXFORD DEPARTMENT OF PUBLIC WORKS

**ENGINEERING** 

600 Unicorn Park Drive ▲ Woburn MA 01801 Phone: 781.932.3201 Fax: 781.932.3413








### **EROSION CONTROL NOTES:**

- 1. PRIOR TO BEGINNING CONSTRUCTION OPERATIONS A SINGLE ROW OF COMPOST FILTER TUBES FILTER TUBES OR EQUAL FOR EROSION CONTROL SHALL BE INSTALLED AS SHOWN ON THIS PLAN. THIS SHALL SERVE AS THE LIMIT OF WORK LINE.
- 2. COMPOST FILTER TUBES SHOULD BE INSTALLED PARALLEL TO THE BASE OF THE SLOPE OR OTHER DISTURBED
- 3. STAKES SHALL BE INSTALLED THROUGH THE MIDDLE OF THE FILTER TUBES AT 10 FT. ON CENTER INTERVALS, USING 2" X2" X36" WOODEN STAKES.
- 4. STAKING DEPTH SHALL BE 12" MINIMUM.
- 5. THE CONTRACTOR SHALL MAINTAIN THE COMPOST FILTER TUBES IN A FUNCTIONAL CONDITION AT ALL TIMES, INCLUDING INSPECTIONS AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. THE CONTRACTOR SHALL IMMEDIATELY CORRECT ANY DEFICIENCIES.CONTRACTOR SHALL REMOVE SEDIMENT DEPOSITS AS NECESSARY TO MAINTAIN THE FILTERS IN WORKING CONDITION.
- FILTER TUBES SHALL BE MAINTAINED UNTIL DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED, OR AS DETERMINED BY THE ENGINEER.
- NO WORK MAY PASS THE LINE OF STAKED FILTER TUBES DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND LAWFUL DISPOSAL OF ALL EXCAVATED MATERIALS AND DEBRIS NOT OTHERWISE REUSED ON THE SITE FOR GRADING PURPOSES



**COMPOST FILTER TUBES** 

NOT TO SCALE

## RESOURCE AREA IMPACTS

SCALE: 1"=10'

## RESOURCE IMPACTS

LAND UNDER WATER (LUW)
------------------------

LUW ADDED	250 S.F.
BVW CONVERTED TO LUW	92 S.F.
LUW LOST	0 S.F.
NET LUW	-342 S.F.
LUW TEMP IMPACT	100 S.F.

TOTAL TEMPORARY AND PERMANENT LUW IMPACT.. . 100 S.F.

# BORDERING VEGETATED WETLAND (BVW)


92 S.F. BVW CONVERTED TO LUW..... 145 S.F. **BVW ADDED..** 570 S.F. BVW TEMP. IMPACT. NET BVW IMPACT. +53 S.F.

TOTAL TEMPORARY AND PERMANENT BVW IMPACT.... . 662 S.F.

## RIVERFRONT RIPARIAN ZONE

RIVERFRONT TEMP. IMPACT......1,800 S.F. RIVERFRONT PERM. IMPACT......1,370 S.F. 40 L.F. RIVER BANK ADDED.. TEMP RIVER BANK IMPACT...

TOTAL RIVERFRONT TEMPORARY AND PERMANENT IMPACTS.... .....3,170 S.F.




## **DEWATERING NOTES**

- 1. INSTALL SEDIMENTATION AND EROSION CONTROLS PRIOR TO BEGINNING WORK.
- 2. ALL WORK SHALL BE CLOSELY COORDINATED WITH THE BOXFORD CONSERVATION COMMISSION OR THEIR DESIGNEE.
- 3. ALL IN-STREAM WORK SHALL BE COORDINATED SO THAT ALL CULVERT REMOVAL AND NEW CULVERT INSTALLATION BEGINS AND IS COMPLETED DURING A PERIOD OF "LOW FLOW" CONDITIONS AND IS PERFORMED IN ACCORDANCE WITH THE ORDER OF CONDITIONS. CONTRACTOR'S PROPOSED WORK SCHEDULE AND VERIFICATION OF WEATHER CONDITIONS SHALL BE SUBMITTED TO THE BOXFORD DEPARTMENT OF PUBLIC WORKS FOR REVIEW AND APPROVAL PRIOR TO COMMENCING WORK.
- 4. DEWATERING SHALL BE USED IF NECESSARY TO ENSURE THAT SOIL COMPACTION, CONCRETE PLACEMENT AND CULVERT INSTALLATION IS PERFORMED "IN THE DRY".
- 5. DIRECT DEWATERING DISCHARGE TO PORTER BROOK IS PROHIBITED.
- DEWATERING EFFLUENT SHALL BE DISCHARGED INTO A WATER FILTRATION BAG SUITABLE FOR THE REQUIRED FLOW AND LOCATED WITHIN A DEWATERING SETTLING BASIN SURROUNDED BY SILT FENCE, LOCATED AS SHOWN ON THE PLANS.
- 7. THE DEWATERING BASIN SHOULD BE PLACED ON REASONABLY LEVEL, STABLE SOIL.
- 8. PUMPS AND HOSES SHALL BE IN GOOD WORKING CONDITION AND OF ADEQUATE CAPACITY FOR THE REQUIRED FLOW.
- 9. ALL EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO COMMENCING DEWATERING OPERATIONS.

## **DEWATERING BAG/BASIN**

NOT TO SCALE




## PROJECT # | 2152008 SCALE AS NOTED DATE | JUNE 28, 2016 DRAFTED BY BFS REV COMMENTS

DATE


**CULVERT DETAILS** KELSEY ROAD CULVERT REPLACEMENT **BOXFORD, MASSACHUSETTS** 

PREPARED FOR: TOWN OF BOXFORD DEPARTMENT OF PUBLIC WORKS


**Bridge & Structural Engineering** Civil/Site Engineering Land Surveying Transportation Engineering Architectural Design & Building Renovations



Phone: 781.932.3201 Fax: 781.932.3413



NOTE: THE BRIDGE RAIL MOUNTING STUDS MUST BE TEMPLATE CAST IN THE HEADWALL AS SHOWN IN THE DETAILS. ALL OTHER METHODS OF MOUNTING ARE PROHIBITED.



PROJECT # 2152008

SCALE AS NOTED


DATE JUNE 7, 2016

DRAFTED BY BFS

# **CULVERT DETAILS**

# PREPARED FOR: TOWN OF BOXFORD DEPARTMENT OF PUBLIC WORKS

**Bridge & Structural Engineering** Civil/Site Engineering Land Surveying Transportation Engineering Architectural Design & Building Renovations




## PRECAST CONCRETE CULVERT NOTES:

- 1. CONTRACTOR SHALL SUBMIT PRECAST CONCRETE CULVERT DESIGN CALCULATIONS AND SHOP DRAWINGS SEALED BY A PROFESSIONAL ENGINEER REGISTERED IN THE COMMONWEALTH OF MASSACHUSETTS FOR APPROVAL PRIOR TO FABRICATION.
- 2. THE CONTRACTOR SHALL APPROVE ALL ELEVATIONS AND DIMENSIONS OF THE SHOP DRAWINGS PRIOR TO FABRICATION.
- 3. ALL CONCRETE SHALL HAVE A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 5000 PSI. CEMENT TO BE TYPE III CONFORMING TO ASTM C-150.
- 4. ALL REINFORCING STEEL SHALL BE GRADE 60 BARS AND CONFORM TO ASTM A615. ALL REINFORCING SHALL BE BENT COLD. UNLESS OTHERWISE NOTED, REINFORCING SPLICE LENGTHS SHALL BE AS FOLLOWS:

BAR SIZE	SPLICE LENGTH (IN)
#8	36
#6	24

- 5. REINFORCEMENT SHALL BE PLACED WITH A MINIMUM OF  $1\frac{1}{2}$ " COVER FROM THE FACE OF CONCRETE.
- 6. THE LOADING FOR THE STRUCTURE IS HL-93 WITH 18" OF SOIL COVER AND 6-1/2" HOT MIX ASPHALT PAVEMENT.
- 7. A PRESUMPTIVE BEARING CAPACITY OF 2000 PSF SHALL BE USED IN THE DESIGN OF THE CULVERT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SUBGRADE PREPARATION SUCH THAT THE DESIGN BEARING CAPACITY SHALL BE ACHIEVED. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IF THIS BEARING CAPACITY CANNOT BE MET.
- 8. CONTRACTOR SHALL SUBMIT AN ERECTION PROCEDURE/SHOP DRAWING FOR APPROVAL PRIOR TO STARTING ANY CONSTRUCTION.





Phone: 781.932.3201 Fax: 781.932.3413

