

SCHEDULE OF INVERTS PROPOSED

SECTION A-A

DETAIL OF SOIL ABSORPTION SYSTEM

4.5

EL=105.40 EL=105.23 EL=105.18 EL=105.0 EL=104.5

೦ೄ

3/4" - 1 1/2" DOUBLE WASHED STONE

INVERT @ FOUNDATION SEPTIC TANK INVERT (IN) SEPTIC TANK INVERT (OUT)

ATERALS INVERT (END) LATERALS INVERT (END) BOTTOM OF STONE BREAKOUT ELEV. ESTIMATED SEASONAL HIGH G.W.

THE PRINCIPAL STRUCK


Off

9"(MIN.) CLEAN FILL-

LIMIT OF REMOVAL OF UNSUITABLE MATERIAL (SEE GEN. NOTE 1)

PUMP CHAMBER INVERT (IN) PUMP CHAMBER INVERT (OUT)

DISTRIBUTION BOX INVERT (IN)
DISTRIBUTION BOX INVERT (OUT)
LATERALS INVERT (START)




## **PUMP NOTES:**


- 1. 8 DOSES/DAY
  DOSE = 330 GDP / 8
  BACKFLOW = 172 LF.x 0.163 g/li=
  28.0 gol.
  69.3 gol.
- H = (69.3) / 10.4 gal. PER INCH = 6.6°
- PUMP ON TO PUMP OFF = 6 INCHES USE 500 gal. COMPARTMENT OF SHEA 1500/500 COMBO TANK, OR APPROVED EQUAL.
- 3. USE BARNES SUBMERSIBLE PUMP MODEL SE 411, 0.4-hp, 115v SINGLE PHASE. (4.75 INCH IMPELLER). INSTALL BALL VAVE TO THEOTILE BACK PUMP TO DELIVER MIN. 35 gpm ◆ T.D.H. = 16'±
- INSTALL HIGH WATER FLOAT LEVEL SENSOR IN PUMP CHAMBER WITH VISIBLE FLASHING ALARM TO BE MOUNTED INSIDE DWELLING, ALARM TO BE SEPARATE CIRCUIT TO ONE POWERING PUMP, LOC. TO COORDINATED WITH OWNER
- 5. PRECAST CONCRETE PUMP CHAMBER SHALL HAVE A 64.2 GAL CAPACITY BETWEEN ON AND OFF LEVELS AND A MINIMUM RESERVE CAPACITY OF ONE DAY'S FLOW.


1,000 GALLON PUMP CHAMBER




6 OUTLET H-20 DISTRIBUTION BOX








1500 GALLON 2 COMP. SEPTIC TANK





IP-1

REFUSAL C 120"(97.7) ESTIMATED HIGH GROUND WATER WATER SEEPING STANDING WATER PERC RATE

Ap FSL GrCos 7.5YR 5/5 C2 GrCos 7.5YR 4/6

TP-2

ESTIMATED HIGH GROUND WATER @ 120"(97.5) WATER SEEPING PERC RATE

## SOIL TESTING

PERFORMED BY: MICHAEL O'NEILL SOLS EVALUATOR - SE13616
WITNESSED BY: KENDELL LOUNGO, TOWN OF BOXFORD B.O.H. DIRECTOR
DATE: MAY 22, 2017

I CERTIFY THAT I PASSED THE EXAMINATION APPROVED BY THE DEPARTMENT OF ENVIRONMENTAL PROTECTION AND THAT THE SOIL EVALUATION WAS PERFORMED BY ME CONSISTENT WITH THE REQUIRED TRAINING, EXPERTISE, AND EXPERIENCE DESCRIBED IN 310 CMR 15.018 (2).

CERTIFIED SOIL EVALUATOR 

## DESIGN

VENT SYSTEM

EXISTING 3 REDROOM DWELLING

3 BEDROOMS © 110 gpd PER BEDROOM = 330 gpd P = 2 MIN. PER. INCH CLASS | SOIL - LTAR=0.74 gpd/sf

REQUIRED AREA: (330 gpd) / (0.74 gpd/sf) = 445 sf

USE 40' x 14' STONE BED AREA PROVIDED: 40' x 14' = 560 sf

-NOTICE-

THIS DRAWING AND ALL ENGINEERING INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY HE PARTY FOR WHOM THE WORK WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. IF YOU ARE NOT SUCH A PARTY, YOU ARE HEKEBY NORHED THAT ANY USE, DISCLOSURE, COPYING, DISTRIBUTION OR THE TANKIE OF ANY ACTION IN RELAKCE ON THIS OR ANY RELATED INFORMATION, PLAN OR REPORT IS STRICT.

FLOW PROVIDED: 560 af x 0.74 = 414 gpc

 $200\% \times 330$  gpd = 660 gol. SEPTIC TANK DESIGN FOR GARBAGE GRINDER — USE 1500 gol. TWO COMPARTMENT TANK (1000g/500g)

4 POND STREET BOXFORD, MASSACHUSETTS


APPLICANT:


MICHAEL SHEEHAN P.O. BOX 850861 BRAINTREE, MA 02184

DATE: JUNE 14, 2017

SCALE: AS NOTED







TOTAL HEAD METERS FEET

- ALL ORGANIC MATERIAL MUST BE REMOVED FROM THE AREA DIRECTLY.
  UNDER AND BEYOND THE PROPOSED SOIL ABSORPTION SYSTEM. THIS
  AREA MUST BE BACKFILLED TO ELEVATIONS INDICATED ON THESE PLANS
  WITH SELECT ON-SITE OF IMPORTED SOIL MATERIAL, CONSISTING OF
  CLEAN GRANULAR SAND OR OTHER GRANULAR MATERIAL, FREE FROM
  GRANIC MATTER AND THER DELETERIOUS SUBSTRACES. MIXTURES AND
  LAYERS SHALL NOT BE USED. THE FILL MATERIAL SHALL MEET THE SPECIFICATIONS OF TITLE 5, SECTION 15.255 (3).
- 2. HEAVY MACHINERY SHALL NOT BE PERMITTED TO PASS OVER THE SOIL ABSORPTION SYSTEM.
- TIGHT JOINT PIPING IS TO CONSIST OF POLYVINYL CHLORIDE PIPE (P.Y.C.) SCHEDULE 40, UNLESS OTHERWISE NOTED.
- ALL DISTURBED AREAS ARE TO BE LOAMED, SEEDED AND MAINTAINED TO PREVENT EROSION:
- 7. THE DESIGNER HAS NOT BEEN RETAINED BY THE CLIENT TO CONSTRUCT OR SUPERVISE THE CONSTRUCTION OF THE SYSTEM. THE CONTRACTOR IS RESPONSIBLE FOR MAKING ARRANGEMENTS FOR INSPECTION OF INSTALLATION OF THE SYSTEM WITH THE LOCAL BOARD OF HEALTH BEFORE BACKFILLING OVER ANY SYSTEM COMPONENTS.
- 8. THE DESIGNER MUST INSPECT AND SURVEY THE INSTALLED SYSTEM PRIOR TO THE CONTRACTOR BACKFILLING OVER ANY SYSTEM COMPONENTS. THE AS-BUILT PLAN MUST BE CERTIFIED BY THE DESIGNER WITH A STAMP AND SYMMETISM.
- 9. PLAN HAS BEEN PREPARED SPECIFICALLY AS A SEPTIC SYSTEM DESIGN PLAN AND IS NOT TO BE USED TO ESTABLISH PROPERTY LINES OR BUILDING SETBACKS. PROPERTY LINES AND BUILDING LOCATIONS ARE GRAPHIC ONLY, PROPERTY LINES NOT HAVING BEEN VERIFIED. NO REPRESENTATION OR CERTIFICATION AS TO THE ACCURACY OF THOSE SHOWN IS IMPLIED OR INTENDED.
- 10. SEE BENCHMARK TABLE ON THIS DRAWING FOR ELEVATION DATUM.
- 11. EXISTING UTILITY LOCATIONS HAVE NOT BEEN VERIFIED. PRIOR TO THE START OF EXCAVATION ACTIVITIES THE CONTRACTOR IS TO CALL DIG-5AFE AT 1-888-344-7233.
- 12. NO CHANGES ARE TO BE MADE TO THE PLAN DURING CONSTRUCTION UNLESS APPROVED BY THE DESIGN ENGINEER AND BOARD OF HEALTH
- THE SYSTEM HAS NOT BEEN DESIGNED TO ACCOMMODATE A GARBAGE DISPOSAL.
- 15. ALL SYSTEM COMPONENTS SHALL BE MARKED WITH MAGNETIC TAPE OR COMPARABLE MEANS IN ORDER TO LOCATE THEM ONCE BURIED, PER TITLE 5, SECTION 15.221(12).

MICHAEL O'NEILL, P.E. Professional Consulting Engineer

153 Main Street • North Reading, MA 01864 • 508-633-231

SUBSURFACE SEPTIC DISPOSAL SYSTEM REPLACEMENT

ASSESSORS PARCEL ID: 25/06/07

DESIGNED BY: M.O'N. DRAWN BY: G.L.E. CHECKED BY: M.O'N PROJECT No: 17-105

SHEET: 2 OF 2 DRAWING: 17105SEP.DWG