

# DALEXCO ENTERPRISES, LLC

---

**10 Cote Ct.**

**Coventry, RI 02816**

**401/821-0036**

**508/971-2992 cell**

**E-mail dalexco@verizon.net**

July 22, 2013

To:

Tim Carrol

Town of Chilmark

Menemsha Beach

## Quote #07222013I

Terms 50% with order, 50% upon completion

Delivery: 3-4 weeks ARO

F.O.B. : Components-New Bedford, MA

We are pleased to provide you with a quotation for the following:

Item	Qty	Description	Unit \$	Extended
1	1	Installation of Edson Supplied peristaltic pump station to include: -- 2" HDPE Pipe with fusion welded joints. -- Stainless steel hardware and hangers -- Mounting of (5) Hydrants and hose racks -- Hard wire (3) Remote start/stop boxes to controls -- Connect discharge plumbing to existing 2" line -- Install new conduit and electrical supply lines from existing breaker panel. Note: Town to provide 3' x 3' x 3" cement pad to mount pump. Pipe "chase" from pad through steel bulkhead to accommodate 2" suction line from pump to dock. (4" min).	\$5,200.00	\$5,200.00

**Total \$5,200.00**

Thank you for the opportunity for your business. Please call with any questions.

Sincerely,



Darryl A. Smith  
Sales Engineer