



www.chilmarkma.gov

TOWN OF CHILMARK CHILMARK, MASSACHUSETTS

TOWN OFFICES:
Beetlebung Corner
Post Office Box 119
Chilmark, MA 02535
508-645-2100
508-645-2110 Fax

April 2, 2018

Mr. John Keene
John Keene Excavation, Inc.
P.O. Box 563
West Tisbury, MA. 02575

Subject: Change Order # 1 – Squibnocket Beach Project

Dear John,

This provides the details for Change Order # 1. The purpose of this change is to protect certain additional archaeological features that were discovered. Would you please provide a cost for executing this Change Order? Here is a brief explanation of the details as shown on the enclosed site plan dated April 2, 2018:

1. Approximately 614 cubic yards of additional fill is required. This is in addition to the estimated 900 cubic yards of fill specified in the Request for Proposals (RFP). Please refer to the revised elevations as shown on the site plan dated April 2, 2018. Essentially, the increased elevations cover the southern half of the new parking lot, the southern section of Squibnocket Road and the cul-de-sac versus the original elevations.
2. The Squibnocket Road pavement will need removal and replacing. The section runs from the southern-most end near the old parking lot up to the southern edge of the trench that was dug across Squibnocket Road for utility lines. This will require the complete removal of the pavement and preparing the surface for re-paving -- from the "existing asphalt cut" as shown on the site plan down to the cul-de-sac.

The original RFP specifications called for approximately 4,100 sq. ft. of paving for the cul-de-sac. The estimate is now a total of approximately 8,300 sq. ft. of paving.

3. To follow up on the retaining wall specifications for the cul-de-sac please notice the specification on the site plan that states the bottom of the stone is at elevation = 2.

Best regards,

Chuck Hodgkinson

