## 60-62 WASHINGTON STREET

## A SITE PLAN

[N

# HUDSON, MASSACHUSETTS


(MIDDLESEX COUNTY)

## OWNER/APPLICANT:

62 WASHINGTON STREET REALTY LLC 62 WASHINGTON STREET HUDSON, MASSACHUSETTS 01749

### ENGINEER:

ENGINEERING DESIGN CONSULTANTS, INC. 32 TURNPIKE ROAD SOUTHBOROUGH, MASSACHUSETTS 01772



MAY 23, 2018

REVISED: JULY 16, 2018
REVISED: AUGUST 15, 2018
REVISED: OCTOBER 5, 2018
REVISED: OCTOBER 9, 2018

#### REQUIRED PERMITS

SPECIAL PERMIT FROM ZONING BOARD OF APPEALS
 BUILDING PERMIT

SHEET LIST:

### SITE PLANS


- 1 COVER SHEET
  - EXISTING CONDITIONS
- 3 PROPOSED LAYOUT
- 4 GRADING & UTILITIES
- 5 LIGHTING & LANDSCAPING
- 6 DETAILS


#### STORMWATER PLANS

1 STORMWATER (SWPPP) PLAN


DATE:	DATE:
TOWN OF HUDSON FIRE CHIEF	TOWN OF HUDSON POLICE CHIEF
DATE:	DATE:








ENGINEERING DESIGN CONSULTANTS, INC.'S LIABILITY FOR THIS PLAN IS LIMITED TO THE EXTENT OF ITS FEE LESS THIRD PARTY COSTS.




8/15/18 | PEER REVIEW COMMENTS 7/16/18 STAFF COMMENTS
0 5/23/18 ISSUED FOR REVIEW
DESCRIPTION



Southborough, Massachusetts ph:(508) 480-0225 fax:(800)832-5781

HUDSON, MASSACHUSETTS

**62 WASHINGTON STREET** HUDSON, MASSACHUSETTS 01749



HUDSON, MASSACHUSETTS 01749


7/16/18 | STAFF COMMENTS

0 5/23/18 ISSUED FOR REVIEW
DATE DESCRIPTION

CHK'D BY:

APRVD BY:


PSB




7/16/18 | STAFF COMMENTS 5/23/18 ISSUED FOR REVIEW DESCRIPTION

APRVD BY:

HUDSON, MASSACHUSETTS 01749





CONSTRUCTION PERIOD POLLUTION PREVENTION AND EROSION AND SEDIMENTATION CONTROL PLAN:

NAME OF PERSON AND ENTITY RESPONSIBLE FOR PLAN COMPLIANCE: \_\_\_\_

2. PROJECT MANAGER OF 60-62 WASHINGTON STREET CONSTRUCTION IS THE CONTACT PERSON, CONTACT NUMBER

3. CONSTRUCTION PERIOD POLLUTION PREVENTION MEASURES: AS DEFINED WITHIN.

4. EROSION AND SEDIMENTATION CONTROL PLAN DRAWINGS: REFER TO PLAN VIEW FOR EROSION CONTROL MEASURE

5. DETAIL DRAWINGS AND SPECIFICATIONS FOR EROSION CONTROL: REFER TO INDIVIDUAL DETAILS FOR INSTALLATION OF EROSION CONTROL MEASURES.

6. VEGETATION PLANNING: THE PROPOSED CONSTRUCTION ACTIVITIES WILL BE PERFORMED WITHIN THE LIMITS OF WORK AREA (SILTATION BARRIER BEING THE LIMIT OF WORK). THE FINAL PROPOSED SURFACE WILL CONSIST OF PAVING AND GRASSED AREAS (REFER TO SEQUENCING BELOW).

7. SITE DEVELOPMENT PLAN: REFER TO PLAN VIEW & APPROVED SITE PLANS.

8. CONSTRUCTION SEQUENCING PLAN: THE FOLLOWING CONSTRUCTION SEQUENCE SHALL BE FOLLOWED:

EROSION CONTROL PROVISIONS IN PLACE AND INSPECTED PRIOR TO ANY AND ALL CONSTRUCTION. ANTI-TRACKING STONE CONSTRUCTION ENTRANCE.

STRIP AND STOCKPILE TOPSOIL. PROVIDE TEMPORARY SEEDING OF STOCKPILE, PLACE SILTATION BARRIER AROUND STOCKPILE AND PLACE TARPS OVER THE STOCKPILE IF NECESSARY.

ROUGH GRADE PROPOSED SITE. EXCAVATE AND CONSTRUCT UTILITIES SYSTEMS. REMOVE UNUSABLE MATERIAL FROM SITE.

INSTALL WATER PIPE, DRAINAGE, VORTSENTRY UNITS, AND OTHER UTILITIES. EROSION CONTROL MEASURES AT NEW DRAINAGE INLETS.

PLACE BASE PAVING. CONSTRUCT BUILDING.

FINAL GRADING. m. LOAM AND SEED ALL DISTURBED AREAS AND LANDSCAPE YARD.

n. FINAL TOP COURSE PAVING. o. REMOVE EROSION CONTROL PROVISIONS UPON STABILIZATION AND FINAL SITE INSPECTION BY APPROVING

9. SEQUENCING OF EROSION AND SEDIMENTATION CONTROLS: EROSION CONTROL PROVISIONS IN PLACE AND INSPECTED PRIOR TO ANY AND ALL CONSTRUCTION.

10. OPERATION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROLS: THE CONTRACTOR/OPERATOR IS RESPONSIBLE FOR MAINTAINING A STABLE SITE. THE OPERATOR SHALL EMPLOY EROSION AND SEDIMENTATION CONTROLS TO PREVENT EROSION AND SEDIMENT RELEASES BEYOND THE SEDIMENT BARRIER. THE EROSION CONTROL MEASURES INDICATED ARE THE MINIMUM THAT SHOULD BE EMPLOYED. THE CONTRACTOR/OPERATOR SHALL EMPLOY ADDITIONAL CONTROLS AS THE ON-SITE CONSTRUCTION EXPERIENCE DICTATES.

INSPECTION SCHEDULE:

INSPECTIONS SHALL TAKE PLACE AT LEAST ONCE EVERY 7 CALENDAR DAYS OR WITHIN 24 HOURS OF THE END OF A STORM EVENT OF 0.25" OF RAIN OR GREATER.

INSPECTION FREQUENCY MAY BE REDUCED TO ONCE A MONTH IF THE ENTIRE SITE IS TEMPORARILY STABILIZED OR RUNOFF IS UNLIKELY DUE TO WINTER CONDITIONS OR EXTREMELY DRY CONDITIONS.

INSPECTIONS MUST BE CONDUCTED BY A PROPERLY AUTHORIZED QUALIFIED PERSONNEL. INSPECTIONS SHALL INCLUDE ALL AREAS OF THE SITE DISTURBED BY CONSTRUCTION ACTIVITIES. INSPECTIONS MUST LOOK FOR EVIDENCE OF POLLUTANTS OR POTENTIAL POLLUTANTS ENTERING THE STORM WATER SYSTEM. SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSPECTED TO ENSURE PROPER OPERATION. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE MUST BE INSPECTED FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING.

12. MAINTENANCE SCHEDULE: REPORTS OF SUMMARIZING THE INSPECTIONS SHOULD BE KEPT AS PART OF THIS CONSTRUCTION PERIOD POLLUTION PREVENTION AND SOIL EROSION AND SEDIMENTATION CONTROL PLAN. AT A MINIMUM THE INSPECTION REPORTS SHALL INCLUDE:

b. NAME. TITLE AND QUALIFICATIONS OF THE PERSONNEL MAKING THE INSPECTION; WEATHER CONDITIONS AT THE TIME OF INSPECTION AND SINCE THE PREVIOUS INSPECTION, INCLUDING A BEST ESTIMATE OF THE BEGINNING OF EACH STORM EVENT THAT OCCURRED, DURATION OF EACH STORM EVENT, APPROXIMATE AMOUNT OF RAINFALL FOR EACH STORM EVENT, AND WHETHER ANY DISCHARGES

CONSTRUCTION NOTES

EROSION CONTROL GRASS MIXTURE (SIDE SLOPE GREATER THAN 4 HORIZONTAL TO 1 VERTICAL) FOLLOWING COMPLETION OF GRADING. THE FOLLOWING SEED MIX SHALL BE


% BY WEIGHT

TYPE OF SEED CREEPING RED FESCUE

WHITE DUTCH CLOVER

SEED AT THE RATE OF 2#/2,000 SF USE THE ABOVE MIX AT THE RATE OF 50#/ACRE AND WITH 1/2 BUSHEL/ACRE OF WINTER RYE

ALL DISTURBED AREAS ARE TO BE LOAMED AND SEEDED WITH A MINIMUM OF 6" OF TOP SOIL SPREAD EVENLY THROUGHOUT. PROVIDE EROSION CONTROL MEASURES AS NECESSARY TO PROVIDE SLOPE STABILITY UNTIL VEGETATION IS ESTABLISHED.



. EROSION CONTROL MEASURES (SEE DETAILS) SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF CONSTRUCTION AS INDICATED. 2. MEASURES SHALL BE TAKEN TO LIMIT THE TRACKING OF MATERIAL FROM THE

SITE ONTO WASHINGTON STREET.

PROPERLY DISPOSED OFF-SITE.

3. DUST SHALL BE CONTROLLED BY SPRINKLING OR OTHER APPROVED MEASURES AS NECESSARY.

. EROSION CONTROL MEASURES ARE TO BE MAINTAINED THROUGHOUT THE CON-

THROUGHOUT CONSTRUCTION, ALL DISTURBED AREAS SHALL BE LOAMED AND SEEDED AND MULCHED AS SOON AS PRACTICABLE IN ORDER TO AVOID OVERLAND TRANSPORT OF SEDIMENT.

STRUCTION PERIOD AND PARTICULARLY AFTER SIGNIFICANT RAINFALL. DILAPIDATED HAYBALES AND SILT STOP SHALL BE REPLACED AS REQUIRED TO MAINTAIN THE INTEGRITY OF THE BARRIER. 5. WITH SLOPES STABILIZED AND FINAL INSPECTION COMPLETE, THE EROSION CONTROL BARRIER SHALL BE REMOVED AND

> SEDIMENTATION & EROSION CONTROL METHODS & **PROCEDURES**

d. DISCHARGES THAT OCCUR AT THE TIME OF INSPECTION; e. LOCATION OF DISCHARGES OR SEDIMENTATION FROM THE SITE: LOCATION OF "BMPs" THAT NEED TO BE MAINTAINED:

CONSTRUCTION PROJECT CLOSEOUT IS COMPLETE.

g. LOCATION OF "BMPs" THAT FAILED TO OPERATE AS DESIGNED OR PROVED INADEQUATE FOR A PARTICULAR


h. LOCATIONS WHERE ADDITIONAL "BMPs" ARE NEEDED THAT DID NOT EXIST AT THE TIME OF INSPECTION; CORRECTIVE ACTION REQUIRED INCLUDING ANY CHANGES TO THIS PLAN.

REQUESTED DURING THE CONSTRUCTION PERIOD, AND MAINTAINED FOR THREE YEARS AFTER FINAL


UNDERGROUND UTILITY LOCATIONS ARE NOT GUARANTEED.


IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY LOCATIONS AND ELEVATIONS OF EXISTING UTILITIES PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION

DIGSAFE IS TO BE NOTIFIED 72 BUSINESS HOURS IN ADVANCE OF CONSTRUCTION. CALL DIGSAFE AT 811



1"=500"






THIS PLAN IS LIMITED TO THE EXTENT OF ITS FEE LESS

THIRD PARTY COSTS.

VERIFY THAT THE SYSTEMS ARE NOT CLOGGED AND ARE DRAINING.


g. THE ESTIMATED ANNUAL MAINTENANCE COST OF THIS STORMWATER MANAGEMENT SYSTEM IS \$500/UNIT.

THE GUTTERS.



f. INFILTRATION SYSTEMS: MAINTENANCE OF THE INFILTRATIVE SYSTEMS WILL NOT BE REQUIRED WITH THE PROPER MAINTENANCE OF BUILDING

GUTTERS AND VORTSENTRY UNITS. INSPECTION FOR EACH THE SYSTEMS SHALL BE PROVIDED ONCE A YEAR THROUGH THE INSPECTION PORT.



CROSS SECTION

EROSION CONTROL BARRIER "A"

NOT TO SCALE

Engineering Design Consultants, Inc. 32 Turnpike Road Southborough, Massachusetts ph:(508) 480-0225 fax:(800)832-5781

DWG & DETO023B

-NATIVE SOIL

EROSION CONTROL BARRIER "B"

60-62 WASHINGTON STREET

DETAIL: EC0002

STORMWATER POLLUTION PREVENTION PLAN 60-62 WASHINGTON STREET

62 WASHINGTON ST. REALTY LLC

**62 WASHINGTON STREET** 

HUDSON, MASSACHUSETTS 01749

PREVENTION PLAN APRIL 20, 2018 DEFINITIVE PLAN NO.:

BACKFILL INPLACE


PROJECT:

HUDSON, MASSACHUSETTS

OWNER/APPLICANT:



WW.RCSEARLES.COM



ARCHITECT OF RECORD J. THOMAS REARDON 7 SUNSET DR NORTHBOROUGH, MA ST 11 UNIT / 3 STORY CONDOMINIUM RESIDENCE 60-62 WASHINGTON HUDSON, MA 10/5/18 DATE: 3/16"=1'-0" SCALE:

NOTES:


SCALE: 3/16"=1'-0
DRAWN BY: RCS

CHECKED BY: RCS

2 OF 4

2

WW.RCSEARLES.COM





60-62 WASHINGTON ST. HUDSON, MA 10/5/18 3/16"=1'-0" RCS CHECKED BY: RCS

NOTES:

WWW.RCSEARLES.COM