

Medway Conservation Commission
Minutes 7/21/11

The Medway Conservation Commission meeting of 7/21/11 was called to order at 8:45 p.m. in The Sanford Hall of the Medway Town Hall. The following members were present: Ken McKay, Tony Biocchi and David Travalini.

Village Street improvements – Present is Mr. Thomas Holder, Director of Public Works, requesting an Order of Conditions for improvements on Village Street. Mr. Holder states he is reintroducing a project from 2001. Funding for this project has been appropriated. He states he is not sure why this project did not happen. On Village Street at the stream you will see a what appears to be a catch basin but there is no catch basin. The flow is just passing through. This was the cause of the calapse. We may be able to get another winter out of this, but did want to introduce this project to you because it will have to be done. Our plan is to remove the improper structure and provide for a much better flow. 102a does best to identify what we plan to do. Going to dig down and remove all drainage structures, use geo fabric and replace with more updated cb. Out let to pipe is 12 inches above rip rap. We will do full roadway excavation father this in and cover with bituminous cb. Replace side walk, guard rail and walk rail. Head wall will be replaced. Mortared block wall to build a footing and head wall. May encounter some water and may have to dewater.

Ken – mass dot requires railing. Allow 3 foot railing redoing side walk from village to center street.

This is what we are intending on north side.

South side = remove jersey barriers and install guard rail. 4 foot duct tank. Ripwarp on slope. Fair amount of erosion to improve the situation. Where there is erosion there is ripwrap. Granite headwall. Granite culvert. Culvert in good shape except for area to improve.

Tony when this was proposed there was a lot of traffic issues and the culvert

Onsite erosion control inspection. Compost and orange snot fence. Silt sack cleaned after every storm event. Open order for neighboring project. Contact the owner and ask to close out and remove the silt fence. Notify agent 24 hours before work. Remove invasives. Boy scouts remove invasives list.

Tony . At the dump this weekend and people were commenting the changes.

Issue order for brundage corner addition.

applicant is not present. Motion made by Mr. Travalini to continue this hearing to the July 21, 2011 meeting at 7:45 p.m. Seconded by Mr. McKay. Unanimous.

Tie down stock piles.

Tom points out catch basins covers are being stolen.

66 Village street

Here to show updated plans. Two locations silt fence with compost sock with two socks in the wetland areas.

Full size plan of details issue 66 Village as per plans with the order to be issued pending receipt of pages with changes. Compost and construction fence doubling up where designated. Areas.

Franklin Creek Lane DEP 216-710

4 Daniels Road – 216-0784 - issue

1 Iarussi Way – 216-0761 - issue per karons inspection

Deny due to lack of evidence of completion of project.