



# Gibson Roofs, Inc.

369 Winter St., Hanover, MA 02339

Ph: 781-826-6344

800-495-6344

Fax: 781-826-8063

March 31, 2017

James McKay  
Town of Millis  
900 Main Street, Room #204  
Veterans Memorial Building  
Millis, MA 02054

RE: Well Building Roof Replacement

Dear Mr. McKay,

GIBSON ROOFS, INC. is pleased to provide the following quotation for your review and consideration.

**Scope of Work: Pump 3**

- Demo existing roofs down to concrete deck.
- Furnish and install 2" polyiso & 1/2" asphalt coated fiberboard adhered to concrete deck.
- Furnish and install 3ply modified bitumen roof system in cold process adhesive. 2 base ply + 1 granule surfaced cap sheet.
- Flash all penetrations per manufacturer's specification.
- Furnish and install new perimeter drip edge flashing at perimeter

**Notes:**

- Work is priced to be performed during normal business hours.
- Crane access needed to perform the work.

*Total Cost for this Project.....\$32,280.00*

Thank you for the opportunity to submit this quotation. If you have any questions or require further information, please feel free to contact the office at 781-826-6344.

Sincerely,

Kevin Gibson  
GIBSON ROOFS, INC.

*Quote is good for 30 days.*



# Gibson Roofs, Inc.

369 Winter St., Hanover, MA 02339

Ph: 781-826-6344

800-495-6344

Fax: 781-826-8063

March 31, 2017

James McKay  
Town of Millis  
900 Main Street, Room #204  
Veterans Memorial Building  
Millis, MA 02054

RE: Well Building Roof Replacement

Dear Mr. McKay,

GIBSON ROOFS, INC. is pleased to provide the following quotation for your review and consideration.

**Scope of Work: Pump 4**

- Demo existing roof down to concrete deck.
- Furnish and install 2" polyiso & 1/2" asphalt coated fiberboard adhered to concrete deck.
- Furnish and install 3ply modified bitumen roof system in cold process adhesive. 2 base ply + 1 granule surfaced cap sheet.
- Flash all penetrations per manufacturer's specification.
- Furnish and install new perimeter drip edge flashing at perimeter

**Notes:**

- Work is priced to be performed during normal business hours.
- Crane access needed to perform the work.

Total Cost for this Project.....\$26,870.00

Thank you for the opportunity to submit this quotation. If you have any questions or require further information, please feel free to contact the office at 781-826-6344.

Sincerely,

Kevin Gibson  
GIBSON ROOFS, INC.

*Quote is good for 30 days.*