

**Tech Specs-**

**A-** Milling- to remove 1.5 inches On Tyringham rd Only Total of 6200 ft x25.5 ft All Millings to be hauled to Highway garage 40 Gould Rd

**B-** Fill- add Hma at a depth of 2"

**C-** End Joints to be milled out at 1.5" deep x 10'xwidth of road to make transition from old to new pavement smooth

**D-** A minumun of 2 10-12 ton Asphalt Rollers to be onsite at all times

**E-** Tack Coat to be applied at .05 gal per sq yd