



- SITE MAINTENANCE NOTES**
1. Erosion control shall be installed before any work shall commence.
  2. Contractor shall verify all existing conditions and grades in the field and report any discrepancies to the Engineer before any work begins.
  3. Contractor shall protect and maintain all existing utilities, structures, and other features on the site.
  4. Locations of underground utilities has been taken from best available information and are not warranted to be correct.
  5. No vehicle disturbance will be permitted outside the limit of work.
  6. Any area disturbed by the contractor, outside the limit of work, shall be restored to original condition at the contractor's expense.
  7. The contractor shall remove all trees, shrubs, and other vegetation within the limit of work, unless otherwise specified.
  8. Contractor shall remove all stumps and roots and dispose of them off-site. Such disposal shall be approved by the Engineer.
  9. Any depression remaining from the removal of a stump shall be filled with topsoil and sodded.
  10. Contractor shall leave and seed all areas to the limits shown on the plan as promptly as possible with topsoil and seed.
  11. The contractor shall provide suitable and adequate means of protection during the work to prevent erosion and infiltration of pollutants to adjacent areas.
  12. Means of protection shall be discussed with and approved by the Engineer and shall be maintained during the work and until all areas have been restored to original condition.
  13. All materials required for erosion control shall be provided by the contractor and shall be approved by the Engineer.

Base of Elevations - Mean Sea Level (M.S.L.)  
 Coordinates Based on Massachusetts  
 Grid Coordinate System

PROJECT NO.	69-152
DATE	10/1/88
SCALE	AS SHOWN
DRAWN BY	SMJ
CHECKED BY	SMJ
DESIGNED BY	SMJ
APPROVED BY	SMJ
DATE	10/1/88
PROJECT NO.	69-152
DATE	10/1/88
SCALE	AS SHOWN
DRAWN BY	SMJ
CHECKED BY	SMJ
DESIGNED BY	SMJ
APPROVED BY	SMJ
DATE	10/1/88