

### PROJECT SUMMARY

The existing 33' X 24' concrete foundation will be demolished. An area of about 5800 Sq. Ft. will be cleaned of top soil and other deleterious materials and will be replaced with clean sand or gravel, free from clays, in preparation for the construction of the proposed septic system.

Excavation for a new 4~~5~~' X 24' foundation will then, if found to be suitable materials, be used to fill the site to the proposed grades as shown on the "Proposed Sewage Disposal System" Plan. (A-1).

An isolated depression (1500 S.F.) at the rear of the property will be filled but an area of equal or greater square footage (noted as replacement area Plan A-1) will be constructed to compensate for this fill.

The adjacent wooded swamp will be protected by installing siltation barrier of hay bales and siltation fence along the rear of the property & will be maintained during construction and until all sloping areas are vegetated.