

- ALL WORK SHALL CONFORM TO THE 310 CMR 15.00 STATE ENVIRONMENTAL CODE TITLE 5, THE RULES AND REGULATIONS OF THE SEEKONK BOARD OF HEALTH AND THE LOCAL UPGRADES APPROVED FOR THIS DESIGN. STRIP ALL TOPSOIL, SUBSOIL AND UNSUITABLE MATERIAL, TREE ROOTS AND STUMPS AND ANY OTHER IMPERVIOUS OR SPECIFIED SOIL IN THE AREA OF THE SYSTEM AND 5 FEET BEYOND THE EDGE OF LEACHING TRENCHES HORIZONTALLY IN ALL DIRECTIONS, WHERE POSSIBLE. AT A MINIMUM THE INSTALLER IS TO STRIP MATERIAL 3" VERTICALLY INTO THE NATURALLY OCCURRING PERVIOUS MATERIAL. REPLACE WITH GRANULAR FILL MEETING THE LATEST SPECIFICATIONS OF 310 CMR 15.255 FILL TO THE LIMITS INDICATED (BREAKOUT). THE CONTRACTOR IS TO REMOVE ALL UNSUITABLE MATERIAL BELOW THE PROPOSED SOIL ABSORPTION SYSTEM PRIOR TO INSTALLATION. SEE DEEP OBSERVATION HOLES SOIL DATA FOR FURTHER INFORMATION.
- YERTICAL LIMITS MAY BE VARIABLE. CONTRACTOR SHALL CONTACT "DIG-SAFE" PRIOR TO CONSTRUCTION. LOCATION OF UTILITIES ON THIS PLAN ARE FROM EXISTING INFORMATION, BUT ARE ONLY TO BE CONSIDERED APPROXIMATE.
- ALL PIPE TO BE 4" P. V. C. SCHEDULE 40, UNLESS OTHERWISE NOTED. SEPTIC TANK AND DISTRIBUTION BOX SHALL BE DESIGNED FOR HS-10, AND SHALL BE PROTECTED FROM
- VEHICULAR TRAFFIC BOTH DURING AND AFTER INSTALLATION.
- PLACE 6" MINIMUM COMPACTED CRUSHED STONE UNDER SEPTIC TANK AND DISTRIBUTION BOX SOIL TESTING FOR THIS PROJECT WAS PERFORMED BY DEN MONSES AND WITNESSED BY THE SEEKONK BOARD OF HEALTH AGENT, MR. CHENEVERT. IF CONDITIONS ENCOUNTERED DURING CONSTRUCTION VARY SUBSTANTIALLY FROM THOSE SHOWN ON THIS PLAN, NOTIFY CAPUTO AND WICK, LTD. AND THE TOWN OF
- GARBAGE GRINDER IS **NOT** ALLOWED WITH THIS DESIGN. INLET AND OUTLET TEES FOR SEPTIC TANK ARE TO BE LOCATED DIRECTLY BELOW ACCESS COVERS. BREAKOUT ELEVATION = 164.00. NO FINISHED GRADE BELOW 164.00 FOR 15 FEET (MINIMUM) FROM THE EDGE
- OF THE CHAMBERS, UNLESS IMPERVIOUS BARRIER IS INSTALLED.
- EXISTING WATER WELLS WERE FOUND WITHIN 200' OF PROPOSED SEWAGE DISPOSAL SYSTEM ARE SHOWN. IT IS RECOMMENDED THAT THE SEPTIC TANK BE INSPECTED TWICE A YEAR, AND BE CLEANED WHEN THE
- SOLIDS ARE LESS THAN 12" BELOW THE OUTLET TEE OR EFFLUENT FILTER. MATERIAL AND EQUIPMENT FROM ALTERNATE MANUFACTURERS MAY BE USED IF EQUAL. APPROVAL FOR ALTERNATE MATERIAL AND/OR EQUIPMENT REQUIRED FROM ENGINEER AND THE TOWN PRIOR TO CONSTRUCTION. FULL SPECIFICATIONS FOR ALTERNATE EQUIPMENT MUST BE PROVIDED BY THE CONTRACTOR.
- THE DESIGNER EXPRESSLY DISCLAIMS ANY RESPONSIBILITY FOR MONITORING, INSPECTING OR SUPERVISING THE ACTUAL CONSTRUCTION WORK. AFTER EXCAVATING AND PRIOR TO INSTALLING ANY IMPORTED MATERIAL, CONTACT THE BOARD OF HEALTH AGENT FOR A BOTTOM OF EXCAVATION INSPECTION. AFTER SYSTEM COMPONENTS ARE IN PLACE AND PRIOR TO BACKFILLING, CONTACT THE DESIGNER TO VERIFY THE LOCATION AND ELEVATION OF SYSTEM COMPONENTS AND PREPARE A RECORD DRAWING AS REQUIRED BY THE BOARD
- THE DESIGNER EXPRESSLY DISCLAIMS ANY RESPONSIBILITY, FOR THE INSTALLATION AND MAINTENANCE OF THE SYSTEM. IT SHALL BE THE RESPONSIBILITY OF THE INSTALLER TO CONSTRUCT THE SYSTEM IN ACCORDANCE WITH 310 CMR 15.00 AND LOCAL BOARD OF HEALTH REGULATIONS INCLUDING APPROVED LOCAL UPGRADES AND THE RESPONSIBILITY OF THE OWNER FOR PROPERLY MAINTAINING THE SYSTEM IN ACCORDANCE WITH 310 CMR 15.00 AND THE LOCAL BOARD OF HEALTH REGULATIONS. REFER TO 310 CMR 15.00 AND THE LOCAL BOARD OF HEALTH REGULATIONS FOR ADDITIONAL INFORMATION CONCERNING THE CONSTRUCTION AND OPERATION OF THE SYSTEM. THE INSTALLER AND OWNER SHOULD REVIEW AND APPLY 310 CMR 15.00 AND THE LOCAL BOARD OF HEALTH REGULATIONS.
- REFER TO 310 CMR 15.00 AND THE LOCAL BOARD OF HEALTH REGULATIONS FOR ADDITIONAL INFORMATION CONCERNING THE CONSTRUCTION AND OPERATION OF THE SYSTEM. THE SYSTEM IS TO BE CONSTRUCTED BY A INSTALLER LICENSED BY THE SEEKONK BOARD OF HEALTH.
- THE CELLAR FLOOR ELEVATION SHOWN HAS BEEN SUGGESTED AS A MINIMUM BASED ON OBSERVED GROUNDWATER CONDITIONS. SINCE THE GROUNDWATER LEVELS FLUCTUATE ANNUALLY, NO WARRANTY OF A DRY CELLAR IS EXPRESSED OR IMPLIED.
- FILL MEETING THE REQUIREMENTS OF 310 CMR 15.255(3) MUST BE PLACED ON SCARIFIED, RELATIVELY DRY NATURAL SOIL. THE CONTRACTOR SHALL PROVIDE FOR DEWATERING AS REQUIRED AND ALL WORK SHALL BE PERFORMED UNDER DRY CONDITIONS PER 310 CMR 15.255(6). THE DISCHARGE WATER MUST BE PROPERLY DISPOSED OF AND SHALL NOT BE A SOURCE OF POLLUTION AND/OR EROSION. 20. INSTALL MAGNETIC TAPE OVER ALL PIPE AND SYSTEM COMPONENTS.
- 21. ALL DISTURBED AREAS NOT DEPICTED TO HAVE OTHER FINAL SURFACE TREATMENT SHALL RECEIVE 4" LOAM
- 22. THE CONTRACTOR MUST BE FAMILIAR WITH THE PROPOSED ALTERNATIVE SOIL ABSORPTION SYSTEM TECHNOLOGY AND MUST STRICTLY FOLLOW MANUFACTURERS INSTALLATION INSTRUCTION AND MA. DEP

DEEP OBSERVATION HOLE Y2K-IO LOG ORIGINAL GROUND ELEVATION =159.8

DEPTH	HORIZON	TEXTURE	COLOR	MOTTLING	OTHER
+3" <i>- 0</i> "	0	-	-	-	-
0 - 36"	В	SANDY LOAM	10 YR 6/8	-	_
36" - 108	3" C	SANDY LOAM	2.5 Y 6/4	COMMON 10 YR 6/8	_
OBSERVI	ED GROUNDWATE	R - NONE	WEE	PING FROM PIT FAC	E - NONE
ESTIMATED S.H.G.W. = 42" (ELEV. 156.3)			PERC. RATE = 16 MPI @ 55"		
DATE OF	TESTING - 9/28	100			

DEED ORGED / ATION HOLE YOU LOD LOC

2.5 Y 5/6

2.5 Y 5/3

ORIGINAL GROUND ELEVATION = 160.2							
DEPTH	HORIZON	TEXTURE	COLOR	MOTTLING	OTHER		
+3" <i>- 0</i> "	0	-	-	-	-		
0 - 40"	В	SANDY LOAM	10 YR 6/2	-	BOULDERS		

OBSERVED GROUNDWATER - NONE WEEPING FROM PIT FACE - NONE

SANDY LOAM

LOAMY SAND

ESTIMATED S.H.G.W. = 44" (ELEV. 156.53) PERC. RATE = 8 MPI @ 59" DATE OF TESTING - 1/10/01 DEEP OBSERVATION HOLE Y2K-II LOG

ORIGINAL GROUND ELEVATION = 159.2 DEPTH HORIZON TEXTURE COLOR MOTTLING OTHER +3" - 0" SANDY LOAM 0 - 24" 10 YR 5/8 24 - 52" SILT LOAM Cdl 2.5 Y 5/6 COMM. IOYR 6/8 BASIL (SIC)

OBSERVED GROUNDWATER - 120" GROUNDWATER READING 3/23/01 - 14" PERC. RATE = 6 MPI @ 72"

40" - 110"

52" - 126"

WEEPING FROM PIT FACE - 118" ESTIMATED S.H.G.W. = 14" (ELEV. 158.03) DATE OF TESTING - 9/28/00

104 GRAVEL

COMMON 10 YR 6/8

TEST PREFORMED BY: TESTING WITNESSED BY: HAROLD CHENEVERT, JR., SEEKONK BOARD OF HEALTH

LEGEND

100 	EXISTING CONTOUR PROPOSED CONTOUR MASSACHUSETTS STANDARD INVERT OF PIPE POLYVINYL CHLORIDE PIPE STANDARD DIMENSION RATIO REINFORCED CONCRETE PIPE CONCRETE (BIT. OR P. C.) BITUMINOUS PORTLAND CEMENT TYPICAL	+ 100.00 X 100.00 T. C. B. C. PL ST DB	FINISHED SPOT GRADE EXISTING SPOT GRADE TOP OF CURB BOTTOM OF CURB PROPERTY LINE SEPTIC TANK DISTRIBUTION BOX DEEP OBSERVATION HOLE
---------	---	--	---

I CERTIFY THAT I HAVE CONTACTED THE SEEKONK WATER DISTRICT FOR THE LOCATION OF THE EXISTING WATER SERVICE CURB STOP FOR PLAT 26 LOT 170 AND WAS INFORMED THAT THERE IS NO CURB STOP CURRENTLY FOR THIS LOT. THE PROPOSED DWELLING WILL BE SERVED BY A PRIVATE WELL TO BE INSTALLED IN CONFORMANCE WITH THE SEEKONK BOARD OF HEALTH REGULATIONS.

NOTICE OF INTENT



SEWAGE DISPOSAL SYSTEM 23 PATRICIA DRIVE ASSESSORS PLAT 26 - LOT 170 SEEKONK, MASSACHUSETTS

SHEET

CAPUTO AND WICK LTD. APRIL 2014

1150 PAWTUCKET AVE. **RUMFORD, R.I.** 02916 401-434-8880