



- ### GENERAL NOTES
- 1) THIS SEWAGE DISPOSAL SYSTEM SHALL BE CONSTRUCTED IN CONFORMANCE WITH THE REGULATIONS OF TITLE 5 OF THE STATE ENVIRONMENTAL CODE AND THE REGULATIONS OF THE LOCAL BOARD OF HEALTH.
 - 2) THE LOCAL BOARD OF HEALTH AND THIS FIRM ARE TO BE NOTIFIED:
 - (A) PRIOR TO BEGINNING CONSTRUCTION IN THE EXCAVATION FOR THE PURPOSE OF PERFORMING AN AS-BUILT INSPECTION
 - (B) PRIOR TO CONSTRUCTING THE SYSTEM FOR THE PURPOSE OF INSPECTION ON THIS DESIGN.
 - 3) CONTRACTOR TO VERIFY ALL UTILITY LOCATIONS PRIOR TO CONSTRUCTION THROUGH DIG SAFE AND OTHER APPROPRIATE AGENCIES REPORT ANY DISCREPANCIES TO THE DESIGN ENGINEER.
 - 4) ALL SEPTIC SYSTEM COMPONENTS SHALL WITHSTAND H-10 LOADING UNLESS LOCATED WITHIN 4'-20' LOADING.
 - 5) WHERE REQUIRED CONTRACTOR WILL REMOVE ALL LOAM, SILT, SAND, AND OTHER UNSUITABLE MATERIAL IN THE AREA BENEATH AND FOR 5 FEET ON ALL SIDES OF THE LEACHING FACILITY. THE CONTRACTOR SHALL REMOVE ALL UNSUITABLE MATERIAL WITH CLEAN COURSE SAND FREE FROM CLAY, FINES OR OTHER UNSUITABLE MATERIAL. REPLACEMENT MATERIAL TO HAVE AN INFLUDE PERC RATE OF TWO MINUTES OR LESS.
 - 6) 4\"/>
 - 7) THIS SYSTEM IS NOT DESIGNED FOR USE WITH A GARBAGE DISPOSAL.

