



CITY OF TORRINGTON
REQUEST FOR QUOTATION - INQUIRY ONLY
This is NOT an order

DATE: July 14, 2010

FROM: CITY OF TORRINGTON

Pennie Zucco, Purchasing Agent
140 Main Street
Torrington, CT 06790

PHONE: (860)489-2225

FAX: (860)489-2547

E-Mail: pennie_zucco@torringtonct.org

INQUIRY NUMBER: ARF0721 RECOAT FLOORS AT ARMORY

To receive consideration your quotation must be received by: **July 21, 2010 at 11:00 AM**

Quote price to perform the following service at the Torrington Armory Building, 153 South Main St. Torrington, CT 06790 for the following:

Project 1: Recoat Gymnasium Floor– Annual Maintenance (consisting of 10,430 sq. ft):

Removal of all gum/tape from floor, covering all floor plates, grit screening with 100/120 grit screens, cleaning with waterless cleaner and applying one coat of 50% oil modified, VOC compliant gymnasium floor finish, then light grit screening with maroon pads, cleaning with waterless cleaner and applying last coat of gym finish.

Project 2: Recoat Kitchen Wood Floor – Annual Maintenance (consisting of approximately 751 sq. ft):

Removal of all gum/tape from floor, covering all floor plates, grit screening with 80/100/120 grit screens, cleaning with waterless cleaner and applying one coat of 50% oil modified, VOC compliant gymnasium floor finish, then light grit screening with maroon pads, cleaning with waterless cleaner and applying second coat of gym finish.

Project 3:

Option 3A – Strip Wax and Repaint Floor, Apply Floor Finish - Early Childhood - Education Center Room (consisting of approximately 756 sq ft):

Removal of all gum/tape from floor, covering all floor plates, remove existing floor wax finish, clean floor, paint existing floor design (five colors), apply one coat of 50% oil modified, VOC compliant polyurethane floor finish, then light grit screening with maroon pads, cleaning with waterless cleaner and applying second coat of polyurethane floor finish.

Option 3B – Re-Finish Floor - Early Childhood Education Center Room (consisting of approximately 756 sq ft):

Removal of all gum/tape from floor, covering all floor plates, drum sand floor, cleaning with waterless cleaner and applying one coat of 50% oil modified, VOC compliant polyurethane floor finish, then light grit screening with maroon pads, cleaning with waterless cleaner and applying second coat of polyurethane floor finish.

Must be licensed and insured, supply references, supply product information, supply MSDS sheets, supply maintenance checklist for after work is completed. All quotes must also include availability to complete work, time required for completing work and time for surface to cure prior to use/play.

Inquiries and scheduling site visits should be directed to J. Brett Simmons, Superintendent of Parks and Recreation at 860-489-2385.