



CITY OF TORRINGTON REQUEST FOR QUOTATION - INQUIRY ONLY

This is NOT an order

DATE: April 5, 2011

FROM: CITY OF TORRINGTON
Pennie Zucco
140 Main Street
Torrington, CT 06790

PHONE: (860)489-2225
FAX : (860)489-2547
E-Mail: pennie_zucco@torringtonct.org

The Purchasing Agent is authorized to offer City based bidders that exceed the lowest bid by up to 6%, the opportunity to match the lowest bid. A City based bidder within the 6% differential who agrees to accept the amount of the lowest bid will be awarded the bid. When multiple City based bidders agree to accept the amount of the low bid then the City based bidders will be invited to submit a new bid, not to exceed the low bid. The bid will then be awarded to the lowest responsive, responsible bidder.

INQUIRY NUMBER: RFQ #RBE0419 REPAIRS TO CITY HALL BLUESTONE FLAGSTONE FRONT ENTRANCE

To receive consideration your quotation must be received by: APRIL 19, 2011 AT 11:00 AM

Contact name _____
Company name _____
Address _____
City, State, Zip _____

Phone # _____
Fax # _____
Address email _____

Quote price delivered to 140 Main Street, Torrington, CT 06790 for the following:

Repairs to City Hall Bluestone Flagstone Front Entrance

The project consists of removal and resetting of approximately 225 square feet of random pattern Bluestone Flagstone at the front entrance of City Hall.

- **Barricade and close front entrance of City Hall with signage (inside and outside of building) directing public to use south side building entrance**
- **Inspect job site to verify condition of all Bluestone Flagstone for reuse.**
- **Removal of Bluestone Flagstone without damage to stone flagging for reuse.**
- **Removal of cement mortar setting bet as necessary for re-setting flagstone.**

- **Replacement of cement mortar setting bed and Bluestone Flagstone to match existing and surface uniformity. Beat and level surface to maintain less than 1/8" surface variation.**
- **Grouting of all joints to match existing.**
- **Installation of pre-molded expansion joint filler at perimeter of Bluestone Flagging adjacent to building walls and top granite step.**
- **Installation of polyurethane caulk at expansion joints.**
- **Application of a non-slip sealer on entire Bluestone entrance area including undisturbed areas, (approximately 450 square feet).**
- **Removal of all materials and final cleanup.**

Contractor must be licensed and insured and supply references with contact information with submitted quote.

Questions pertaining to project can be addressed to Public Works Director, Jerry Rollett @ 860-489-2232.

Cost for completed project _____